# LateralX LX5+: Why aren't the heart rate contact plates working?

Follow this troubleshooting guide to help resolve issues with the heart rate contact sensors on the BowFlex LateralX LX5+.

#### Some common complaints may include:

- Heart rate does not register
- Heart rate is erratic or intermittent

#### Follow these steps to troubleshoot the issue


Tools you may need:

Phillips head screwdriver (if removing console from mast)

- 1. If you have not removed the protective film covering the heart rate sensors yet, please do so now. Test to see if your heart rate is displayed [13300.A].
- 2. If the issue persists, ensure your hands are centered on the heart rate sensors with equal pressure. Try to move as little as possible without touching the metal frame [13300.B].
- 3. Dry or heavily calloused hands may need a heart rate cream to make better contact. **Buh-Bump Heart Rate Cream** is a recommended cream to use and can be found at various retailers online [13300.C].
- 4. Check that the connections between the handlebars and the console are secure [13300.D].
- 5. Your heart rate may spike at a high rate when initially touching the contact plates. This is normal and will leve out after a couple of minutes. Try to keep your hands still during this time [13300.E]. If you need a quicker heart rate reading, a heart rate chest strap monitor may be a better option. If you do not have one already, you can order a Heart Rate Chest Strap (see Heart Rate Monitor Compatibility by Model) [13300F].
- 6. Move all devices generating wireless or Wi-Fi signals into another room, preferably on the other side of the house. This includes the wireless chest strap [13300.6].
- 7. If the issue persists, remove the console mast end cap and inspect the cables inside the console mast (**reference 1**). One at a time, unplug and inspect the cables and connectors for damage, such as crimps, cuts, or bent pins. If the cables are undamaged, plug them back in and retest your machine [13300.H]. If damage is present or the issue persists, order a Static Handlebar [13300.I].

(Reference 1)

about:blank 1/3



Inspect and reseat the cables located under the console mast end cap.

### **Need to order replacement parts?**

## 1 Parts Reference Table

Part Description	Part SKU
Static Handlebar	8014278

## 2 Contact Tech Team / Advanced Troubleshooting

about:blank 2/3

If the issue was not resolved in the steps listed, contact the Tech Team or send an Advanced Troubleshooting case.

**Submit a Case** with case type **Advanced Troubleshooting** 

about:blank 3/3